



Project: Famworker's Village Access Road Culvert Replacement
 Task: Contractor Bid Tabs
 Prepare AA Date: 2/26/2018
 Checke DW Date: 2/26/2018

ID	DESCRIPTION	QTY	UNIT TYPE	UNIT PRICE	TOTAL PRICE
GE-1	MOBILIZATION	1	LS		\$
GE-2	PROVIDE / MAINTAIN "AS BUILT" PLANS (SIGNED AND SEALED)	1	LS		\$
GE-3	PROVIDE CONSTRUCTION SURVEYING AND LAYOUT	1	LS		\$
GE-4	MAINTENANCE OF TRAFFIC	1	LS		\$
GE-5	FLOATING TURBIDITY BARRIER	112	LF		\$
GE-6	CLEARING AND GRUBBING ¹	1	LS		\$
GE-7	REGULAR EXCAVATION (APPROX. 1,700 CY)	1	LS		\$
GE-8	EMBANKMENT (APPROX. 1,700 CY)	1	LS		\$
GE-9	1 1/2" ASPHALTIC CONCRETE TYPE S-III (TWO LIFTS)	205	SY		\$
GE-10	6" LIMEROCK BASE	213	SY		\$
GE-11	12" STABILIZED SUBGRADE	222	SY		\$
GE-12	MISC. ASPHALTIC CONCRETE (GUARDRAIL BASE)	79	SY		\$
GE-13	RIPRAP (RUBBLE) DITCH LINING (1.5' THICK) (INCLUDES GEOTEXTILE FABRIC)	296	SY		\$
GE-14	GUARDRAIL	233	LF		\$
GE-15	ROUNDED END ANCHORAGE ASSEMBLY (TYPE II)	2	EA		\$
GE-16	MID SPAN GUARDRAIL SPLICE	2	EA		\$
GE-17	PERFORMANCE TURF (SOD)	367	SY		\$
GE-18	BOX CULVERT INSTALLATION ²	1	LS		\$
GE-19	SIGNING AND STRIPING	1	LS		\$
GE-20	FINISH GRADING	1	LS		\$
GE-21	ALLOWANCE FOR GENERAL ITEMS	1	LS	\$ 75,000.00	\$ 75,000.00
GE-22					\$

TOTAL CONTRACT AMOUNT = \$

- Notes:** 1. CLEARING AND GRUBBING INCLUDES ALL DEMOLITION AND REMOVAL ON-SITE (EXISTING PIPE, PAVEMENT, GUARDRAIL, ETC.)
 2. OWNER RESPONSIBILITY INCLUDES PURCHASE OF BOX CULVERT AND DELIVERY TO SITE